

GREENVILLE UTILITIES COMMISSION
QUESTIONS AND ANSWERS FOR 22-36
RFB FOR GCP-10112 VOA SITE C ROAD GAS IMPROVEMENTS
TUESDAY, JUNE 7, 2022, 2:00PM

1. Silt fence, straw wattles, included in the lay price?

In accordance with Technical Specification 3.10 Erosion & Sedimentation Control, the cost of any and all equipment, materials, and labor required for erosion and sediment control shall be included in the cost per acre (TS 3-9).

2. Can the dry bores on this project be performed as HDD?

The contractor will be allowed to install pipe by HDD in lieu of dry bore for convenience; however, it will be paid at the dry bore unit price.

3. Can the project be performed by HDD instead of open trench?

The contractor will be allowed to install pipe by HDD in lieu of open cut for convenience; however, it will be paid at the open-cut unit price.

4. Does drill under HWY264 (STA 18+00) Need to be wire line located?

The Contractor shall utilize the proper tracing equipment to adequately locate and steer all Horizontal Directional Drills.

5. Are there any time restrictions on the roadways?

Roadway time restrictions are defined in the NCDOT Encroachment Agreement included in the Exhibits. Item 25 on Page 4 of the Agreement states "Traffic shall be maintained at all times. All lanes of traffic are to be open during the hours of 7:00 A.M. to 9:00 A.M. and from 4:00 P.M. to 6:00 P.M. Monday through Friday, during anytime of inclement weather, or as directed by the District Engineer. Any violation of these hours will result in ceasing any further construction by the Encroaching Party or their contractor."

6. Do you have a copy of the approved permits for trench and backfill requirements?

All the permits for this project are included in the Exhibits. See Detail 9 on D3, "TYPICAL POLYETHYLENE (PE) PIPE TRENCH INSTALLATION DETAIL" for instructions on backfilling the pipeline trench.